## Performance versus Tradition. HydroTurf®



See how HydroTurf® compares to other storm water management revetment systems.

	Installed Cost (\$/SF)	Hydraulic Performance	Installation Rate	Aesthetics	Performs Under Settlement	Maintenance
HydroTurf®	\$5 - \$8 /SF	Excellent	Moderate	Yes	Yes	Minimal
Rock Riprap	\$4 - \$10 /SF	Poor	Moderate	No	No	High
Articulated Concrete Block	\$10 - \$18 /SF	Good	Slow	Depend	No	Moderate
Concrete	\$8 - \$12 /SF	Excellent	Slow	No	No	Minimal
Gabions / Reno Mattresses	\$8 - \$14 /SF	Good	Slow	Depends	No	High
Fabriform	\$6 - \$9 /SF	Poor	Moderate	No	No	Moderate - High
Geocell	\$4 - \$8 /SF	Poor - Good	Slow	Depends	Depends	Moderate - High

<sup>\*</sup> All costs are estimates and may vary depending upon project size, geographic location and market conditions.



## Minimize Traffic on Your Right-of-Way



HydroTurf® reduces the overall number of truckloads to the job site.

Truckloads Required Per Product							
SF	HydroTurf®	4.5 Concrete	6" ACB's	24" Riprap			
5,000	2	5	8	25			
10,000	3	9	16	50			
25,000		23	32	125			
50,000	10	45	64	250			
100,000	17	90	128	500			